



नेपाल प्रशासनिक प्रशिक्षण प्रतिष्ठान

जावलाखेल, ललितपुर

मर्मत सम्भार सम्बन्धी कार्यको सिलबन्दी बोलपत्र आह्वानको सूचना

(प्रथम पटक सूचना प्रकाशित मिति: २०७७/१०/९)

यस प्रतिष्ठानको परिसरभित्रका क्याफ्टेरिया भवन, प्रज्ञान सदन (रिसोर्स सेण्टर) र डाइनिङ्ग हलको मर्मत सम्भार सम्बन्धी कार्य गराउनु पर्ने भएको हुँदा इजाजत प्राप्त ईच्छुक फर्म/कम्पनीले बोलपत्र फाराममा उल्लिखित शर्तहरूको अधीनमा रही सिलबन्दी बोलपत्र पेश गर्न यो सूचना प्रकाशित गरिएको छ । बोलपत्र फाराम खरिद गर्न फर्म/कम्पनीले आधिकारिक पत्र, दर्ता प्रमाण-पत्र, मूल्य अभिवृद्धि कर प्रमाण-पत्र र आ.व. २०७६/०७७ को कर चुक्ता प्रमाण-पत्र पेश गर्नु पर्नेछ । यस सम्बन्धी विस्तृत जानकारीका लागि प्रतिष्ठानको खरिद इकाईमा सम्पर्क राख्नुहुन अनुरोध छ ।

अनुमानित लागत: रु.१,०९,९३,५६२/४९ (कन्टिन्जेन्सी र मूल्य अभिवृद्धि कर बाहेक)

क्र. सं.	कार्यहरूको विवरण	फाराम दस्तुर	फाराम खरिद गर्ने अन्तिम मिति	फाराम बुझाउने अन्तिम मिति र समय	फाराम खोलिने मिति र समय
१.	मर्मत सम्भार सम्बन्धी कार्य (क्याफ्टेरिया भवन, प्रज्ञान सदन (रिसोर्स सेण्टर) र डाइनिङ्ग हल)	रु.३,०००/-	मिति २०७७ फागुन १० गते, सोमवारसम्म (कार्यालय समयभित्र)	मिति २०७७ फागुन ११ गते, मंगलवार दिनको १२:०० बजेसम्म	मिति २०७७ फागुन ११ गते, मंगलवार दिनको १२:३० बजेपछि

क्याफ्टेरिया भवन, प्रज्ञान सदन (रिसोर्स सेण्टर) र डाइनिङ्ग हल मर्मत सम्भार कार्य सम्बन्धी बोलपत्रदातालाई जानकारी तथा शर्तहरू

- क्याफ्टेरिया भवन, प्रज्ञान सदन (रिसोर्स सेण्टर) र डाइनिङ्ग हल मर्मत सम्भार (यसपछि मर्मत सम्भार कार्य भनिएको) कार्य सम्बन्धी बोलपत्र फाराम यो सूचना प्रथम पटक प्रकाशित भएको मितिले ३०औं दिनसम्म कार्यालय समयभित्र रु.३,०००/- (तीनहजार मात्र) (फिर्ता नहुने) तिरी यस प्रतिष्ठानबाट खरिद गर्न सकिनेछ र ३१औं दिनको १२:०० बजेभित्र सिलबन्दी बोलपत्र फाराम यस प्रतिष्ठानमा दर्ता गरिसक्नु पर्नेछ । दर्ता भएका सिलबन्दी बोलपत्र फारामहरू सोही दिनको १२:३० बजेपछि बोलपत्रदाता वा निजको मञ्जुरीनामा पत्र सहितको प्रतिनिधिहरूको रोहवरमा खोलिनेछ । फर्म/कम्पनीको आधिकारिक पत्र र परिचय-पत्र विना बोलपत्रदाता तथा फर्म/कम्पनीले दिएको मञ्जुरीनामा पत्र र परिचय-पत्र विना बोलपत्रदाताको प्रतिनिधिलाई बोलपत्र खोल्ने स्थानमा प्रवेश दिइने छैन । बोलपत्रदाता वा निजको प्रतिनिधि उपस्थित नभएमा पनि बोलपत्र खोल्न कुनै बाधा पर्ने छैन ।
- सिलबन्दी बोलपत्र फारामसाथ निम्नलिखित कागजपत्रहरू अनिवार्य रूपमा पेश गर्नु पर्नेछ:**
 - फर्म/कम्पनी दर्ता प्रमाण-पत्र (नवीकरण भएको/सम्बन्धित कार्य गर्न इजाजत प्राप्त भएको) को प्रमाणित प्रतिलिपि
 - स्थायी लेखा नम्बर दर्ता तथा मूल्य अभिवृद्धि कर दर्ता प्रमाण-पत्रको प्रमाणित प्रतिलिपि
 - आ.व.२०७६/७७ को कर चुक्ता प्रमाण-पत्रको प्रमाणित प्रतिलिपि
 - बोलपत्र जमानत बापत रु.३,४७,४०५/- (तीनलाख सतचालीसहजार चारसय पाँच) मेगा बैंक नेपाल लिमिटेड, जावलाखेल शाखामा यस प्रतिष्ठानको नाममा रहेको खाता नं.००७००१०९६३२३४ मा नगद दाखिला गरेको सक्कल बैंक भौचर वा मान्यता प्राप्त "क" वर्गको वाणिज्य बैंकले यस प्रतिष्ठानको नाममा जारी गरेको र बोलपत्र फाराम पेश गर्ने अन्तिम मितिदेखि गणना हुने गरी कम्तीमा १२० (एकसय बीस) दिन म्याद भएको बैंक ग्यारेण्टीको सक्कल प्रति

- (ड) बोलपत्रदाताले खरिद कारवाहीमा भाग लिन अयोग्य नभएको, प्रस्तावित खरिद कारवाहीमा आफ्नो स्वार्थ नवाभिएको र सम्बन्धित पेशा वा व्यवसाय सम्बन्धी कसूरमा आफूले सजाएँ नपाएको भनि लिखित रुपमा गरेको घोषणाको सक्कल प्रति
- (च) पावर अफ एटर्नीको सक्कल प्रति
३. बोलपत्र फाराम खरिद गर्न ईच्छुक फर्म/कम्पनीले आधिकारिक पत्र, स्थायी लेखा नम्बर, मूल्य अभिवृद्धि कर दर्ता, आ.व. २०७६/७७ को कर चुक्ता प्रमाण-पत्रको प्रतिलिपि पेश गरेपछि मात्र बोलपत्र फाराम दिइनेछ । बोलपत्रदाताले यस प्रतिष्ठानबाट वितरित बोलपत्र फाराम नै प्रयोग गर्नु पर्नेछ । अन्य तवरले प्राप्त बोलपत्र फाराम मान्य हुने छैन ।
 ४. जुन फर्म/कम्पनीले बोलपत्र फाराम खरिद गरेको हो सोही फर्म/कम्पनीबाट मात्र बोलपत्र फाराम पेश गर्न पाइनेछ ।
 ५. बोलपत्र फारामको प्रत्येक पानामा बोलपत्रदाताको आधिकारिक सही तथा फर्म/कम्पनीको छाप लागेको हुनु पर्नेछ र बोलपत्रको खाम बाहिर “नेपाल प्रशासनिक प्रशिक्षण प्रतिष्ठान” तथा “मर्मत सम्भार कार्य सम्बन्धी बोलपत्र” उल्लेख गरेको हुनु पर्नेछ ।
 ६. बोलपत्र फाराम विक्री गर्ने, दर्ता गर्ने अन्तिम दिन र खोले दिन सार्वजनिक विदा वा प्रतिष्ठानमा विदा पर्न गएमा क्रमशः विदापछि कार्यालय खुलेको दिन उल्लिखित समय र स्थानमा बोलपत्र फाराम विक्री गर्ने, दर्ता गर्ने तथा खोले कार्य हुनेछ
 ७. सिलबन्दी नभएको, म्याद नाघी आएको, रित नपुगेको, कुनै शर्त राखिएको वा बुँदा नं. २ मा उल्लिखित कागजपत्रहरू पेश नभएको बोलपत्र उपर कुनै कारवाही गरिने छैन र मूल्याङ्कन प्रक्रियामा समावेश गरिने छैन ।
 ८. बोलपत्रदाताले बोलपत्र फारामको BoQ मा उल्लिखित सबै आइटमहरूका लागि अनिवार्य रुपमा रकम कबोल गर्नु पर्नेछ । सबै आइटमहरूका लागि रकम कबोल नगर्ने बोलपत्र उपर कुनै कारवाही गरिने छैन र मूल्याङ्कन प्रक्रियामा समावेश गरिने छैन ।
 ९. बोलपत्र फाराममा आफूले कबोल गरेको प्रति इकाई मूल्य अंक र अक्षर दुवैमा स्पष्ट बुझिने गरी छुट्टाछुट्टै लेख्नु पर्नेछ । अंक र अक्षरको बीचमा फरक पर्न गएमा अक्षरमा अंकित मूल्यलाई मान्यता दिइनेछ । बोलपत्र फाराममा आफूले कबोल गरेको प्रति इकाई मूल्य र जम्मा मूल्यमा फरक पर्न गएमा प्रति इकाई मूल्यलाई मान्यता दिइनेछ । बोलपत्र फाराममा केरमेट भएमा केरमेट गरिएको ठाउँमा बोलपत्रदाताले सही गर्नु पर्नेछ ।
 १०. कुनै कारण जनाई वा नजनाई बोलपत्र स्वीकृत गर्ने वा नगर्ने वा रद्द गर्ने वा घटी वा बढी अंकको बोलपत्र स्वीकृत गर्ने वा नगर्ने वा आंशिक रुपमा स्वीकृत गर्ने वा नगर्ने सम्पूर्ण अधिकार यस प्रतिष्ठानमा सुरक्षित रहनेछ
 ११. बोलपत्र स्वीकृत भएको १५ (पन्ध्र) दिनभित्र प्रतिष्ठानमा सम्झौता गर्न आउन स्वीकृत बोलपत्रदातालाई जानकारी गराइनेछ । सम्झौता गर्न आउँदा कार्यसम्पादन जमानत (परफरमेन्स ग्यारेण्टी) बापत **प्रतिष्ठानले तोके अनुसारको** रकम मेगा बैंक नेपाल लिमिटेड, जावलाखेल शाखामा यस प्रतिष्ठानको नाममा रहेको खाता नं.००७००१०१६३२३४ मा नगद जम्मा गरेको सक्कल बैंक भौचर वा मान्यता प्राप्त “क” वर्गको बाणिज्य बैंकले यस प्रतिष्ठानको नाममा जारी गरेको र सम्झौता भएको मितिले कम्तीमा १५ (पन्ध्र) महिनाको म्याद भएको बैंक ग्यारेण्टीको सक्कल प्रति पेश गर्नु पर्नेछ । तोकिएको अवधिभित्र सम्झौता गर्न नआएमा स्वीकृत बोलपत्रदाताको बोलपत्र जमानत रकम जफत गरी नियमानुसार प्रक्रिया अगाडि बढाइनेछ ।
 १२. सम्झौतामा सही गर्न फर्म/कम्पनीको आधिकारिक पत्र र परिचय-पत्र सहित स्वीकृत बोलपत्रदाता आफै वा फर्म/कम्पनीले दिएको मञ्जुरीनामा पत्र र परिचय-पत्र सहितको आफ्नो प्रतिनिधि तथा एक जना साक्षी सहित उपस्थित हुनु पर्नेछ ।
 १३. स्वीकृत बोलपत्रदाताले मर्मत सम्भार सम्बन्धी कार्यका लागि आफूले मूल्य अभिवृद्धि कर सहित कबोल गरेको कूल रकम बराबरको र कम्तीमा १ (एक) वर्ष अवधिको निर्माण बीमाका साथै बोलपत्रदाताको तर्फबाट मर्मत सम्भार कार्यमा संलग्न हुने जनशक्तिहरू तथा प्रतिष्ठानले तोकेको संख्या अनुसारको जनशक्तिको बीमा गरेको सक्कल कागजपत्र पेश गर्नु पर्नेछ ।
 १४. बोलपत्र पेश गर्ने बोलपत्रदाताको बोलपत्र जमानत स्वीकृत बोलपत्रदाता र प्रतिष्ठानबीच सम्झौता भएपछि फिर्ता गरिनेछ ।
 १५. मर्मत सम्भार सम्बन्धी कार्यको लागि प्रतिष्ठान र स्वीकृत बोलपत्रदाताबीच हुने सम्झौताको म्याद दुवै पक्षबाट सम्झौतामा सही भएको मितिले सम्झौतामा उल्लिखित अवधिसम्म कायम रहनेछ ।

१६. बोलपत्र फाराममा उल्लिखित मर्मत सम्भार सम्बन्धी कार्यको आइटम, परिमाण, ड्रइङ्ग, डिजाइन तथा नक्शामा प्रतिष्ठानको आवश्यकता अनुसार हेरफेर भएमा, थपघट भएमा वा प्रतिष्ठानले भेरिएशन आदेश दिएमा स्वीकृत बोलपत्रदाताले स्वीकार गर्नु पर्नेछ ।
१७. बोलपत्र फाराममा उल्लिखित मर्मत सम्भार सम्बन्धी कार्यको आइटम तथा परिमाणमा प्रतिष्ठानको आवश्यकता अनुसार हेरफेर तथा कार्यको परिमाणभन्दा थप कार्य गराउनु परेमा स्वीकृत बोलपत्रदाताले सम्झौतामा उल्लेख भएको मूल्यमा नै थप कार्य अनिवार्य रूपमा गर्नु पर्नेछ ।
१८. स्वीकृत बोलपत्रदाताले प्रतिष्ठानले कार्यादेश दिएको मितिले ९० (नब्बे) दिनभित्र सम्झौता अनुसार, बोलपत्र फाराममा उल्लेख भए अनुसार र प्रतिष्ठानले तोके अनुसार मर्मत सम्भार सम्बन्धी सम्पूर्ण कार्यहरू सम्पन्न गरिसक्नु पर्नेछ ।
१९. स्वीकृत बोलपत्रदाताले गरेका मर्मत सम्भार तथा सोसंग सम्बन्धित अन्य सबै सामानहरूको मर्मत सम्भार, आवश्यक परेमा सामानहरू समेत फेर्ने, साट्ने तथा त्रुटी सच्याउने सम्बन्धमा कम्तीमा १ (एक) वर्ष वारेण्टी/त्रुटी सच्याउने अवधि रहनेछ । वारेण्टी/त्रुटी सच्याउने अवधिभित्र गरिने त्रुटी सच्याउने कार्य, मर्मत सम्भार, फेरिने तथा साटिने सम्बन्धित सामानहरूको कुनै पनि भुक्तानी प्रतिष्ठानले गर्ने छैन । प्रतिष्ठानले तोकेको कर्मचारी वा प्राविधिक वा परामर्शदाताबाट मर्मत सम्भार सम्बन्धी कार्यको प्राविधिक चेकजाँच गराई सो कार्य उपयुक्त भएको प्रतिवेदन प्राप्त भएपछि तथा प्रतिष्ठानले कार्यस्वीकार गरेपछि मात्र वारेण्टी/त्रुटी सच्याउने अवधि गणना गरिनेछ । साथै वारेण्टी/त्रुटी सच्याउने अवधिभित्र गरिने त्रुटी सच्याउने कार्य, मर्मत सम्भार, सामानहरू फेर्ने तथा साट्ने आदि कार्यका लागि प्रतिष्ठानले निर्देशन दिएको ७ (सात) दिनभित्र स्वीकृत बोलपत्रदाताले सम्पन्न गरिसक्नु पर्नेछ । सामानहरू फेर्ने तथा साट्नेको लागि प्रतिष्ठानबाट बुझिलिई लैजाने र प्रतिष्ठानमा फिर्ता ल्याउने व्यवस्था बोलपत्रदाता आफैले गर्नु पर्नेछ ।
२०. स्वीकृत बोलपत्रदाताले मर्मत सम्भार सम्बन्धी कार्यमा प्रयोग गर्ने तथा अन्य सम्बन्धित सबै सामानहरूको गुणस्तर तथा स्पेसिफिकेशन सम्झौता अनुसार, बोलपत्र फाराममा उल्लेख भए अनुसार र प्रतिष्ठानले तोके अनुसारको हुनु पर्नेछ ।
२१. स्वीकृत बोलपत्रदाताले मर्मत सम्भार सम्बन्धी कार्यमा प्रयोग गर्ने सम्बन्धित सबै सामानहरूको गुणस्तर जाँचका साथै मर्मत सम्भार सम्बन्धी कार्यको प्रत्येक चरणको जाँच प्रतिष्ठानले तोकेको कर्मचारी वा प्राविधिक वा परामर्शदाताले गर्नेछ । जाँचका क्रममा देखिएका त्रुटीहरू सच्याउन प्रतिष्ठानले तोकेको कर्मचारी वा प्राविधिक वा परामर्शदाताले दिएको निर्देशन स्वीकृत बोलपत्रदाताले अनिवार्य रूपमा पालना गर्नु पर्नेछ ।
२२. स्वीकृत बोलपत्रदाताले मर्मत सम्भार सम्बन्धी कार्य गर्दा प्रतिष्ठानका सामानहरू टुटफुट वा नोक्सान भएमा प्रतिष्ठानले निर्धारण गरे अनुसार क्षतिपूर्ति वापतको रकम स्वीकृत बोलपत्रदाताले प्रतिष्ठानलाई बुझाउनु पर्नेछ । यस्तो रकम प्रतिष्ठानले स्वीकृत बोलपत्रदातालाई भुक्तानी दिनुपर्ने रकम वा स्वीकृत बोलपत्रदाताको कार्यसम्पादन जमानत वापतको रकमबाट असूल गर्न सक्नेछ ।
२३. प्रतिष्ठानमा मर्मत सम्भार सम्बन्धी कार्यको क्रममा लाग्ने अन्य सम्बन्धित आवश्यक सामानहरूको कुनै पनि भुक्तानी प्रतिष्ठानले गर्ने छैन । स्वीकृत बोलपत्रदाता आफैले व्यहोर्नु पर्नेछ ।
२४. स्वीकृत बोलपत्रदाताले सम्झौता अनुसार कार्य नगरेमा वा गरेका कार्यहरू सम्झौता अनुसार, बोलपत्र फाराममा उल्लेख भए अनुसार र प्रतिष्ठानले निश्चित गरेको गुणस्तर तथा स्पेसिफिकेशन अनुसारको नभएमा प्रतिष्ठानले मर्मत सम्भार सम्बन्धी कार्य अन्यत्रबाट गराउन सक्नेछ । यसरी कार्य गराउँदा सम्झौतामा उल्लिखित रकमभन्दा बढी लागेमा बढी लागेको रकम प्रतिष्ठानले स्वीकृत बोलपत्रदाताबाट असूल गरिनेछ वा प्रतिष्ठानले सम्झौता खारेज गरी स्वीकृत बोलपत्रदाताको कार्यसम्पादन जमानत (परफरमेन्स ग्यारेण्टी) रकम जफत गरी नियमानुसार प्रक्रिया अगाडि बढाइनेछ ।
२५. स्वीकृत बोलपत्रदातालाई मर्मत सम्भार सम्बन्धी कार्यका लागि प्रतिष्ठानले कुनै पनि पेशकी (एडभान्स पेमेण्ट) दिने छैन ।
२६. स्वीकृत बोलपत्रदातालाई मर्मत सम्भार सम्बन्धी सम्पन्न कार्य परिमाण र इकाई दरको आधारमा बढीमा ३ (तीन) रनिङ्ग बिलमा प्रतिष्ठानले निम्न अनुसार रकम भुक्तानी गरिनेछः
 (क) पहिलो रनिङ्ग बिल: सम्पूर्ण भौतिक कार्यहरूको औषतमा ४० (चालीस) प्रतिशत भौतिक कार्य सम्पन्न भएपछि स्वीकृत कबोल रकमको २५ (पच्चीस) प्रतिशतले हुने रकम
 (ख) दोस्रो रनिङ्ग बिल: सम्पूर्ण भौतिक कार्यहरूको औषतमा ८० (असी) प्रतिशत भौतिक कार्य सम्पन्न भएपछि स्वीकृत कबोल रकमको २५ (पच्चीस) प्रतिशतले हुने रकम

- (ग) तेस्रो तथा अन्तिम बिल: सम्पूर्ण कार्यहरू सम्पन्न भएपछि तथा प्रतिष्ठानले सो कार्यस्वीकार गरेपछि स्वीकृत कबोल रकमको ५० (पचास) प्रतिशतले हुने रकम
२७. पहिलो तथा दोस्रो रनिङ्ग बिलको भुक्तानीका लागि स्वीकृत बोलपत्रदाताले तोकिए अनुसार मर्मत सम्भार कार्य सम्पन्न भएको कागजपत्र पेश गर्नु पर्नेछ र सो कार्य प्रतिष्ठानले तोकेको कर्मचारी वा प्राविधिक वा परामर्शदाताबाट प्राविधिक चेकजाँच गराई सम्पन्न भएको कार्य उपयुक्त भएको प्रतिवेदन तथा भुक्तानीका लागि सिफारिस प्राप्त भएपछि मात्र भुक्तानी गरिनेछ । तेस्रो तथा अन्तिम बिलको भुक्तानीका लागि स्वीकृत बोलपत्रदाताले मर्मत सम्भार सम्बन्धी सम्पूर्ण कार्यसम्पन्न भएको प्रतिवेदन तथा कार्य भए अनुसारको ड्रइङ्ग पेश गर्नु पर्नेछ र सो कार्य प्रतिष्ठानले तोकेको कर्मचारी वा प्राविधिक वा परामर्शदाताबाट प्राविधिक चेकजाँच गराई सम्पन्न भएको कार्य उपयुक्त भएको प्रतिवेदन, भुक्तानीका लागि सिफारिस प्राप्त भएपछि तथा प्रतिष्ठानले सो कार्य स्वीकार गरेपछि मात्र भुक्तानी गरिनेछ ।
२८. प्रतिष्ठानमा मर्मत सम्भार सम्बन्धी कार्य गरे वापत तिर्न बुझाउनु पर्ने कर, शुल्क, महसुल वा अन्य यस्तै भुक्तानी गर्नु पर्ने सबै दायित्वहरू स्वीकृत बोलपत्रदाताको हुनेछ ।
२९. स्वीकृत बोलपत्रदातालाई प्रतिष्ठानबाट गरिने भुक्तानी रकमबाट नियमानुसार लाग्ने करकट्टी गरी मात्र भुक्तानी दिईनेछ ।
३०. मर्मत सम्भार सम्बन्धी कार्यको वारेण्टी/त्रुटी सच्याउने अवधि समाप्त भएपछि मात्र नियमानुसार कार्यसम्पादन जमानत (परफरमेन्स ग्यारेण्टी) रकम बिना ब्याज फिर्ता गरिनेछ ।
३१. बोलपत्र सम्बन्धी कुनै संशोधन गर्नु परेमा सो को जानकारी प्रतिष्ठानको सूचना पाटीमा टाँस गरिनेछ ।
३२. प्रतिष्ठान र स्वीकृत बोलपत्रदाताबीच हुने सम्झौता सम्बन्धमा कुनै विवाद उठेमा श्रीमान् कार्यकारी निर्देशकज्यू, नेपाल प्रशासनिक प्रशिक्षण प्रतिष्ठानको निर्णय अन्तिम हुनेछ र हुने निर्णय प्रतिष्ठान र स्वीकृत बोलपत्रदाता दुवैलाई मान्य र अन्तिम हुनेछ ।
३३. बोलपत्र फाराम तथा प्रतिष्ठान र स्वीकृत बोलपत्रदाताबीच हुने सम्झौतामा उल्लिखित शर्तहरू बाहेक अन्य कुराको हकमा प्रतिष्ठान र स्वीकृत बोलपत्रदाता दुबैको आपसी सहमति बमोजिम हुनेछ ।
३४. यस जानकारी तथा शर्तमा उल्लेख नभएका कुराहरूको हकमा बोलपत्र फाराम तथा यस प्रतिष्ठानको आर्थिक प्रशासन सम्बन्धी नियमावली, २०६८ बमोजिम हुनेछ ।
३५. यस सम्बन्धी विस्तृत जानकारीका लागि प्रतिष्ठानको खरिद इकाईमा सम्पर्क राख्न सकिनेछ ।

Description of Works

1. Project: Repairing and Maintenance of Cafeteria

S. No.	Description of Works	Quantity	Unit
A	Repair and Maintenance of Cafeteria		
1	Site Clearance before and after completion of works including leveling, sweeping, shifting and cleaning all complete works as per instruction of site engineer.	1.00	Job
2	Taking out Doors, Pan, Washbasin and Commode safely all complete works as per specification and instruction of site engineer.	11.00	Nos.
3	Providing and fixing readymade teak wood door shutter all complete work as per specification and instruction of site engineer.	13.00	Sq.M.
4	Taking out tiles of toilet and kitchen safely all complete works as per instruction of site engineer.	349.03	Sq.M.
5	Supplying and fixing porcelain glazed tile (1:4) cement with border as per specification and instruction of site engineer.	349.03	Sq.M.
6	Providing Mosquito Proof Net on windows all complete works as per specification and instruction of site engineer.	25.50	Sq.M.
7	Providing 38 mm khpa with Mosquito Proof Net on windows all complete work as per specification and instruction of site engineer.	0.15	Cu.M.

S. No.	Description of Works	Quantity	Unit
8	Providing 5 mm glass on windows all complete work as per specification and instruction of site engineer.	56.24	Sq.M.
9	Providing and applying 2 coats primer and 1 coat enamel paint all complete works as per specification and instruction of site engineer.	361.87	Sq.M.
10	Supplying and applying 2 coats emulsion painting on internal wall all complete works as per specification and instruction of site engineer.	514.33	Sq.M.
11	Taking out and dismantling of roof tile (Telia) and screeding in safely as per instruction of site engineer.	395.00	Sq.M.
12	Supplying and fixing 1.2 mm flexible water proofing plastic sheet membrane containing HDPE on roof for water proofing as per specification and instruction of site engineer.	471.50	Sq.M.
13	Providing and supplying silicon paint out side cafeteria building all complete works as per specification and instruction of site engineer.	679.67	Sq.M.
14	12.5 mm thick in 1:4 ratio mortar cement sand plaster with punning in perfect line and level as per specification and instruction of site engineer.	49.68	Sq.M.
15	38 mm thick screeding with cement, sand and chips in 1:4 ratio all complete works as per specification and instruction of site engineer.	395.00	Sq.M.
16	Supplying and fixing telia tile in perfect line and level in 1:4 ratio mortar all complete works as per specification and instruction of site engineer.	395.00	Sq.M.
17	Supplying, filling and covering in expansion joint with thermacool and asphalt tape as per specification and instruction of site engineer.	41.00	R.M.
18	Taking out existing 20 Nos. of lights all complete works as per instruction of site engineer.	40.00	Nos.
19	Cleaning and maintaining the ventilations of 16 Nos. all complete works as per instruction of site engineer.	16.00	Nos.
20	Taking out (Dismantling) safely manhole and pipeline as per instruction of site engineer.	1.00	Job
21	Applying and fixing P.C.C. 1:2:4 ratio with mixing and vibrating in perfect line and level as per instruction of site engineer.	0.76	Cu.M.
22	38 mm concret flooring (1:2:4) screeding as per specification and instruction of site engineer.	51.15	Sq.M.
23	Applying and fixing local made 1st class brick in 1:4 ratio in perfect line and level as per instruction of site engineer.	0.10	Cu.M.
24	Supplying and fixing 18"x18" CI metal frame cover of manhole all complete work as per instruction of site engineer.	1.00	Sq.M.
25	Supplying and applying 2 coats chapara polish all complete works as per instruction of site engineer.	60.00	R.M.
B	Sanitary Works		
26	Supplying and fitting 580 mm Orissa Pan with low level cistern all complete set fitting as per specification and instruction of site engineer.	2.00	Set
27	Supplying and fitting white glazed porcelain clay one piece commod with flushing cistern, p or s trap, seat cover all complete fitting as per specification and instruction of site engineer.	2.00	Set
28	Supplying and fitting 55x40 cm washbasin European pattern complete set as per specification and instruction of site engineer.	5.00	Set

S. No.	Description of Works	Quantity	Unit
29	Supplying and fitting German standard Hand Dryer all complete set as per specification and instruction of site engineer.	2.00	Set
30	Supplying and fixing mirror all complete set 6'*3' as per specification and instruction of site engineer.	2.00	Set
31	CP Glass Shelf as per specification and instruction of site engineer.	2.00	Set
32	Supplying and fixing CP commod spray as per specification and instruction of site engineer.	4.00	Set
33	Recess Soap Dish (American Standard Cotto) as per specification and instruction of site engineer.	2.00	Set
34	PVC 115 mm with all fitting pipe including washer, connector and angle connector all complete works as per specification and instruction of site engineer.	30.48	R.M.
35	Repair and maintenance of dish washbasin and washbasin plumbing as per instruction of site engineer.	6.00	Job
36	Supplying and fixing 15 mm C.P. basin Mixer Single Lever with 450 mm long Braided Hoses all complete fittings as per specification and instruction of site engineer.	6.00	Job
C	Electrical Works		
37	Supplying and fitting 18W led tubelights with holder as per specification and instruction of site engineer.	25.00	Set
38	Supplying and fixing 7/22 Trishakti Nepali Copper Cable or equivalent as per specification and instruction of site engineer.	100.00	R.M.
39	Supplying and fixing 12 mm PVC listy as per specification and instruction of site engineer.	100.00	R.M.

2. Project: Repairing and Maintainance of Pragyan Sadan (Resource Centre)

S. No.	Description of Works	Quantity	Unit
A	Repair and Maintenance of Resource Centre		
1	Site clearance before and after completion of works including leveling, sweeping, shifting and cleaning all complete works as per instruction of site engineer.	1.00	Job
2	Taking out Doors, Pan, Washbasin, and Commode safely all complete works as per instruction of site engineer.	17.00	Nos.
3	Dismantling of ladies and gents toilet's tiles safely all complete works as per instruction of site engineer.	70.51	Sq.M.
4	Dismantling of ladies and gents toilet's brick wall safely all complete works as per instruction of site engineer.	16.24	Cu.M.
5	Providing and fixing 18 mm Alstone Hybrid Board (Wooden Polymer Composite-WPC Board) Altwood, Ecoste, Alstone or equivalent.	20.64	Sq.M.
6	Providing and fixing Brass Locking set (L-Drop) as per specification and instruction of site engineer.	8.00	Set
7	Providing and fixing white glazed clay tile in perfect line and level as per instruction of site engineer.	78.96	Sq.M.
8	Providing and fixing readymade teak wood door shutter all complete work as per specification and instruction of site engineer.	5.02	Sq.M.

S. No.	Description of Works	Quantity	Unit
9	Taking out choukos of window as per instruction of site engineer.	5.00	Job
10	Supplying and fixing 1st class local brick in 1:4 cement, sand mortar in perfect line and level as per drawing and instruction of site engineer.	2.02	Cu.M.
11	Providing and applying 12.5 mm plaster in 1:4 ratio sand cement mortar inside tile in perfect line and level as per instruction of site engineer.	76.41	Sq.M.
12	Providing and applying 2 coats Plastic Emulsion paint in internal wall as per specification and instruction of site engineer for complete work.	79.07	Sq.M.
13	Providing and applying 2 coats Enamel paint as per specification and instruction of site engineer for complete work.	5.60	Sq.M.
B	Sanitary Works		
14	Supplying and fitting white glazed porcelain clay one piece commode with flushing cistern, P or S trap, seat cover all complete fitting as per specification and instruction of site engineer.	2.00	Set
15	Supplying and fitting 580 mm Orissa Pan with low level cistern all complete set fitting as per specification and instruction of site engineer.	2.00	Set
16	Supplying and fitting 55x40 cm washbasin European pattern complete set as per specification and instruction of site engineer.	4.00	Set
17	Supplying and fitting Mirror 6'*3' all complete fitting as per site engineer.	2.00	Set
18	Supplying and fitting 15 mm die CPVC pipe with (T/Elbow/Socket/Reducer etc.) all complete fitting as per specification and instruction of site engineer.	18.29	R.M.
19	Supplying and fitting toilet paper holder complete fitting as per specification and instruction of site engineer.	4.00	Set
20	Supplying and fitting urinal (61x41x38) cm with all complete fitting set as per specification and instruction of site engineer.	3.00	Set
21	Supplying and fitting white glazed porcelain clay (68x30) cm Division Plate all complete set as per specification and instruction of site engineer.	2.00	Set
22	Supplying and fitting Commod/Pan Cp spray 1.5 CM. spray as per specification and instruction of site engineer.	4.00	Set
23	Supplying and fitting 150 mm PVC pipe with (T/Elbow/Socket/Reducer etc.) complete fitting as per specification and instruction of site engineer.	4.00	R.M.
C	Electrical Works		
24	Supplying and fitting 4 Gang Switch with complete fitting as per site engineer.	3.00	Set
25	Supplying and fitting wall and ceiling light, switch box with complete fitting as per instruction of site engineer.	4.00	Set
26	Supplying and placing 18W Led Tubelight fitting with all fitting as per specification and instruction of site engineer.	8.00	Set
27	Supplying and placing 18W Led Surface Mount light including all fitting works as per specification and instruction of site engineer.	6.00	Set

3. Project: Repairing and Maintenance of Dining Hall

S. No.	Description of Works	Quantity	Unit
A	Repair and Maintenance of Dining Hall		
1	Site Clearance before and after completion of works including leveling, sweeping, shifting and cleaning all complete works as per design, drawing, specification and instruction of site engineer.	1.00	Job

S. No.	Description of Works	Quantity	Unit
2	E/W Excavation in Dinning Kitchen Drainage Pipe line as per site condition and instruction of site engineer.	10.00	Cu.M.
3	Taking out existing 4 sets of Pans safely as per instruction of site engineer.	4.00	Set
4	Taking out existing 1 set of cloth bath top safely as per instruction of site engineer.	1.00	Set
5	Taking out existing 1 nos. of Door safely as per instruction of site engineer.	1.00	Nos.
6	Taking out existing 3 nos. of Wooden Ply door safely as per instruction of site engineer.	3.00	Nos.
7	Taking out wooden ply of partition as per instruction of site engineer.	2.00	Job
8	Taking out existing 6 nos. of toilet door (D/2.12) safely as per instruction of site engineer.	6.00	Nos.
9	Taking out and shifting to another place and re-fix on same place of water tank on roof all complete works as per instruction of site engineer.	1.00	Job
10	Supplying and fixing Readymade Teak Wood door complete work as per specification and instruction of site engineer.	30.57	Sq.M.
11	Site clearance before and after completion of including in taking out pipe line, group cutting, table shifting etc. as per instruction of site engineer.	1.00	Job
12	Providing and applying 2 coats emulsion paint on internal wall all complete works as per specification and instruction of site engineer.	538.69	Sq.M.
13	Supplying and applying 2 coats Nepal Red Paint in perfect texture as per specification and instruction of site engineer.	644.55	Sq.M
14	Providing and applying 2 coats Enamel Paint on doors, windows, wall and wooden partition as per specification and instruction of site engineer.	392.14	Sq.M
15	Applying 3 coats chapra polish on table as per specification and instruction of site engineer.	171.30	Sq.M
16	Taking out Telia tile safely and screeding below tile all complete works as per instruction of site engineer.	504.00	Sq.M.
17	Supplying and filling and covering in expansion joint with Thermacool and Asphalt Tape as per specification and instruction of site engineer.	42.00	R.M.
18	Supplying and fixing 1.2 thick flexible water proofing membrane consisting HDPE carrier plastic sheet membrane as per specification and instruction of site engineer.	594.00	Sq.M
19	Applying 38 mm screeding mixing cement, sand and chips in perfect line and level all complete works as instruction of site engineer.	634.00	Sq.M
20	Supplying and fixing Telia tile in perfect line and level in 1:4 cement and sand ratio all complete works as per instruction of site engineer.	504.00	Sq.M
21	Taking out 15 mm plaster safely as per instruction of site engineer.	53.64	Sq.M
22	Applying 15 mm plaster and punning in perfect line and level as per site engineer.	135.93	Sq.M
23	Applying 15 mm scorting in perfect line and level as per instruction of site engineer.	44.00	R.M.
24	Taking out existing tile of toilet all the complete works as per instruction of site engineer.	196.22	Sq.M.
25	Providing and fixing white glazed digital tyle 2'x2' & 9"x1' inside kitchen and infront of toilet.	196.22	Sq.M.

S. No.	Description of Works	Quantity	Unit
26	Taking out of existing 8 nos. of water proof light bulbs as per instruction of site engineer.	8.00	Nos.
27	Taking out of existing 30 nos. of light bulbs as per instruction of site engineer.	30.00	Nos.
28	Providing and applying 9" local made brick in 1:4 cement sand as per instruction of site engineer.	2.12	Cu.M.
29	Providing and fixing 5'x5' metal cover for manhole as per instruction of site engineer.	1.00	Set
30	Supplying and fitting 580 mm Orissa Pan with low level cistern complete set as per specification and instruction of site engineer.	3.00	Set
B	Sanitary Works		
31	Supplying and fixing 55x40 cm washbasin European pattern complete set as per specification of site engineer.	8.00	Set
32	Supplying and fixing Mirror all complete set 6'*3' as per specification and instruction of site engineer.	1.00	Set
33	Providing and fitting PVC pipe (115 mm=21.33 R.M., 150 mm=15 R.M.) all set as per specification and instruction of site engineer.	36.33	R.M.
34	Providing and fitting 32 mm CPVC Pipe SDR 13.5, 22.5 kg sqcm as per specification and instruction of site engineer.	15.00	R.M.
35	Maintenance for the washbasin all complete works as per instruction of site engineer.	6.00	Job
C	Electrical Works		
36	4 Gang 1 Way switch	8.00	Nos.
37	Led 11W Bulb	30.00	Nos.
38	Water Proof Light	8.00	Nos.
39	3-22 copper wire Trishakti of equiyant	100.00	R.M.
40	PVC Listy	20.00	R.M.